

15H-355

Qty	Length (ft)	Total Length	OD	Min Thk	Unit Weight (lb/ft)	Total Weight (lb)	Description
47.00	21.60	1034.40		0.33	7.38	7337.29	Lot Total
							Tube, Boiler, Straight, 1 3/4 OD, 0.220 in min wall thk, plain ends, bare, 2 1/4 croloy, seamless cold drawn, asme SA213 GR T22
1	19.00	19.00	1.75	0.220	3.59	68.30	Qty-1-19'5,3-25'
3	25.00	75.00	1.75	0.220	3.59	269.62	
							Tube, Boiler, Straight, 2 1/4 OD, 0.388 in min wall thk, plain ends, bare, 2 1/4 croloy, seamless cold drawn, asme SA213 GR T22
1	32.00	32.00	3.25	0.388	11.86	379.51	Qty-1-32', 1-22'7
1	22.58	22.58	3.25	0.388	11.86	267.79	
							Tube, Boiler, Straight, 2 1/4 OD, 0.403 in min wall thk, plain ends, bare, 2 1/4 croloy, seamless cold drawn, asme SA213 GR T22
1	19.50	19.50	2.25	0.403	7.95	155.02	Qty-1-19'5, 1-22'4
1	22.33	22.33	2.25	0.403	7.95	177.51	
							Tube, Boiler, Straight, 2 1/2 OD, 0.543 in min wall thk, plain ends, bare, 2 1/4 croloy, seamless cold drawn, asme SA213 GR T22
2	24.00	48.00	2.50	0.543	11.35	544.76	Qty-2-24', 6-22'7
6	22.58	135.48	2.50	0.543	11.35	1537.58	
							Tube, Boiler, Straight, 2 1/2 OD, 0.165 in min wall thk, plain ends, bare, 2 1/4 croloy, seamless cold drawn, asme SA213 GR T22
1	25.08	25.08	2.50	0.165	4.11	103.20	Qty-1-25'1
							Tube, Boiler, Straight, 2 1/4 OD, 0.225 in min wall thk, plain ends, bare, 1 1/4 Croloy seamless cold drawn,, asme SA 213 GR T11
5	26.25	131.25	2.25	0.225	4.87	638.67	Qty-5-26'3, 3-25'5
3	25.42	76.26	2.25	0.225	4.87	371.09	
							Tube, Boiler, Straight, 1 3/4 OD, 0.247 in min wall thk, plain ends, bare, 2 1/4 Croloy seamless cold drawn,, asme SA 213 GR T22
3	23.58	70.74	2.25	0.221	4.79	338.77	QTY-3-23'7,2-20'7
2	20.58	41.16	2.25	0.221	4.79	197.12	
							Tube, Boiler, Straight, 2 5/8 OD, 0.555 in min wall thk, plain ends, bare, 1/2 Croloy seamless cold drawn,, asme SA 213 GR T2
1	22.50	22.50	2.63	0.555	12.27	276.07	QTY-1-22'6
							Tube, Boiler, Straight, 2 1/2 OD, 0.305 in min wall thk, plain ends, bare, 2 1/4 Croloy seamless cold drawn,, asme SA 213 GR T22
2	9.92	19.84	2.50	0.305	7.15	141.86	Qty-2-9'11, 1-11'2,1-15'2
1	11.17	11.17	2.50	0.305	7.15	79.87	
1	15.17	15.17	2.50	0.305	7.15	108.47	
							Tube, Boiler, Straight, 2 1/4 OD, 0.332 in min wall thk, plain ends, bare, 2 1/4 Croloy seamless cold drawn,, asme SA 213 GR T22
2	23.67	47.34	2.25	0.332	6.80	321.95	Qty-2-23'8,10-20'
10	20.00	200.00	2.25	0.332	6.80	1360.15	