

15H-356

Qty	Length (ft)	Total Length	OD	Min Thk	Unit Weight (lb/ft)	Total Weight (lb)	Description
17	15.62	267.40		0.28	5.23	1397.47	Lot Total
							Tube, Boiler, Straight, 2" OD, 0.288 in min wall thk, plain ends, bare, 304h croloy, seamless cold drawn, asme SA213 GR TP304H
4	22.00	88.00	2.00	0.288	5.27	463.39	Qty-4-22', 1-13'6, 2-9',1-13',1-17' 1
1	13.50	13.50	2.00	0.288	5.27	71.09	
2	9.00	18.00	2.00	0.288	5.27	94.79	
1	13.00	13.00	2.00	0.288	5.27	68.46	
1	17.08	17.08	2.00	0.288	5.27	89.94	
							Tube, Boiler, Straight, 2 1/4" OD, 0.248 in min wall thk, plain ends, bare, 304 croloy, seamless cold drawn, asme SA213 GR TP304H
6	12.08	72.48	2.25	0.248	5.30	384.33	Qty-6-12'-1
							Tube, Boiler, Straight, 2" OD, 0.269 in min wall thk, plain ends, bare, 304 Croloy seamless cold drawn,, asme SA 213 GR TP304H
2	22.67	45.34	2.00	0.269	4.97	225.48	Qty-2-22'8